



<b>Rehabilitation / Construction of Water Supply Schemes (7'x4'x4.0')</b>						
Particulars of item and	No.	L	B	H/D	Qty	Unit
Detail of works		Ft	Ft	Ft		
<b>Plain Cement concrete in 1:4:8</b>						
PCC	4.00	2.00	2.00	0.25	4.00	Cft
<b>Total PCC</b>					<b>4.00</b>	<b>Cft</b>
<b>Brick Masonary</b>						
Walls Masonary (6" thick)	1.00	7.00	4.00	0.50	14.00	Cft
Wall Masonary	4.00	7.00	0.50	4.00	56.00	Cft
Column Masonary	4.00	2.00	1.50	4.00	48.00	Cft
Animal Tank	1.00	5.00	5.00	2.00	50.00	Cft
<b>Sub Total=</b>					<b>168.00</b>	<b>Cft</b>
<b>Roof Tile</b>						
Roof Tile	1.00	7.00	4.00		28.00	Sft
Shade Tile	1.00	4.00	3.00		12.00	Sft
<b>Sub Total=</b>					<b>40.00</b>	<b>Sft</b>
<b>Plaster 1:4</b>						
Walls outer side	4.00	7.00		4.00	112.00	Sft
Walls Inner side	4.00	7.00		4.00	112.00	Sft
Shade	1.00	7.00	3.00		21.00	Sft
Shade Front	1.00	7.00	0.25		1.75	Sft
<b>Total plaster</b>					<b>246.75</b>	<b>Sft</b>
<b>Tile</b>						
Outer Side Tile	1.00	7.00		4.00	28.00	Sft
Outer Side Tile	1.00	7.00	3.00		21.00	Sft
<b>Total=</b>					<b>49.00</b>	<b>Sft</b>