



Sindh Agricultural & Forestry Workers Coordinating Organization (SAFWCO)  
Building resilience of flood affected communities supported by Oxfam GB  
in Tehsil Faiz Gunj, District Khairpur mir's



Excavation/Re-Excavation of Water Ponds for Storage and Uses of Water Where Ground Water is Not Available or Not Suitable Due to High Salinity (20'x20'x8.0')					
S.No	MATERIALS	Qty	UNIT	UNIT RATE	TOTAL COST
1	Excavation	2878.750	Cft		
2	Backfilling	2029.675	Cft		
3	PCC Concrete	115.563	Cft		
4	RCC Concrete (bottom Slab, Top Slab, Walls)	849.075	Cft		
5	Reinforcement Steel	1.350	Ton		
7	Plaster	2128.000	Sft		
8	Paint Work	2128.000	Sft		
<b>Total Amount=</b>					